DRY CONSTRUCTION SYSTEMS

Adrienn LEPEL - BUTE

Dry construction systems

- □ Prefabricated elements → assembly on site
- \square Minimal use of water \rightarrow "dry" construction systems
 - Assembled partitions
 - Suspended ceilings
 - Raised floor systems
 - Dry screeds, dry linings
 - Prefabricated elements of loadbearing structures

Finishing works





Dry construction systems

- Materials
 - Timber
 - Metal (steel)
 - Precast reinforced concrete
- Technologies
 - (Traditional technology)
 - On-site assembly small elements
 - On-site assembly panels
 - Log houses
- Construction systems
 - "Light" construction: weight of outer walls is less than 300kg/m²



Regulation

- Standards and other
 - ÖNORM B 2310: Prefabricated buildings Definitions (independent from the material)
 - ONORM B 2320: Wooden residential houses Technical requirements
 - REGULATION (EU) No 305/2011 harmonised conditions for the marketing of construction products – doesn't contain specific information on dry construction systems
 - ETAG
 - For metal frames;
 - For timber frames;
 - For log houses.
 - Approval for a whole system

Metal frames

- Material is cold formed or hot rolled galvanised steel
 - C studs, I beams, U beams etc.
- □ The frame is cut and packed in a factory
- □ The package is transported to the site
- The frame is assembled on a previously completed foundation/basement connections are made with screws
- Installing insulation, covering, wires pipes, doors and windows etc.





Metal frames

- Packages are available:
 - model homes, ready plans,
 - customisation or individual plans,
 - production using architectural plans
- Packages contain:
 - Engineered drawings (architectural, structural drawings)
 - Structural elements: studs, joists, trusses, purlins, connector plates, steel to steel fasteners, etc.
 - OR prefabricated panels: wall frames, ceiling panels roof panels
 - Optional: panels, claddings, doors and windows, etc.





Metal frames




Metal frames




Timber frames

- Skeleton frame
 - Standardised dimensional lumber
 - Nailed/screwed connections (nailing plates)
- Lining/covering
 - OSB sheathing board
 - Plywood
 - Gypsum board, plasterboard
 - Fiber cement panels
- Insulation, waterproofing, moisture barrier



Timber frames



Timber frames

Technology:

- Low level prefabrication elements cut and labelled in factory;
- Mid-level prefabrication wall-, roof-, slab panels are produced: frame and lining;
- High level prefabrication wall-, roof-, slab panels are ready-made in factory, with coverings, claddings, doors and windows, wires, etc.

 On-site assembly – speed, demand on equipment depends on the level of prefabrication





Timber frames

□ Technology steps:

- Choosing the preferred house style from catalogues
- A fixed price quote with a guaranteed completion date is given
- 3. Selecting finishes, fixtures and fittings
- 4. The wall and roof panels for the house, pre-fitted with doors, windows, service ducts, sockets and insulation, are precision-engineered in the factory
- 5. The panels arrive on site by truck, the team of skilled tradesmen start to work
- 6. The house is roofed and watertight within four days
- 7. The house is ready in 8-12 weeks



Timber frames

- Prefabrication
 - In a factory professional environment
 - One level high wall panels from edge to edge









Timber frames

□ Prefabrication, details







Timber panels

- □ Solid wood panels: cross laminated timber
 - Walls and slabs are prefabricated
 - Assembly on site
 - Complementary layers: heat insulation, rendering, internal covering
 - Measures: thickness: 94-500 mm, height: max. 2950 mm,
 - Lenght: max. 16500 mm.





Timber panels

□ Solid wood panels: production







Timber panels



Log houses

Log types

- Handcrafted only peeled
- □ Milled (machine-profiled) consistent in size and appearance
- Material usually artificially dried and/or glue laminated constant quality
- Full-round logs;
- D-shape logs;
- Square logs;
- Swedish Cope logs;
- Sandwich structures heat insulated.





Log houses

- Prefabrication: beams
- Each beam is numbered and the position is indicated





Log houses

Construction:

- The first row of beams is laid out on the basement ceiling/floor slab and measured with precision.
- Following on from this, the log beams are laid out in the same sequence as their numbering.





Dry construction systems

- □ Supposed advantages:
 - □ Full service (design, build, finance);
 - Fixed prices;
 - Fast construction;
 - Guaranteed quality;
 - Low energy consumption...
- Supposed disadvantages:
 - Lifespan;
 - Safety (storm, burglary, fire ...);
 - No thermal mass...
- □ It depends on the chosen technology and the contractor!

Dry construction systems

- □ Facts in case of approved product and qualified contractor:
 - The construction time can be planned prefabrication is independent from local conditions. On-site activities: mainly assembly.
 - Well-planned building.
 - Very precise construction.
 - Improving regulation.

Dry construction systems

- □ Problem-sources:
 - Problems with the planning using a system
 - Different regulation at the production and the construction
 - Self-made realisation
 - Foundation/basement is usually made by a different contractor
 - □ Fast construction → lots of trader, workers at the same time
 - Quality of the assembly
 - Coordination and control of the processes
 - Quality of the materials (panels!)
 - Transportation and storing
 - Use (maintenance, fixing on the walls, etc.)

References

- http://www.steel-frame.co.nz/
- http://www.kodiaksteelhomes.com/
- http://en.wikipedia.org/wiki/Prefabricated_building
- http://en.wikipedia.org/wiki/Framing_(construction)
- http://en.wikipedia.org/wiki/Log_house
- □ http://www.elkbuildingsystems.com/index.php?id=home&language=en
- http://www.barnahomes.com/
- http://www.woodwill.hu/index.php?lang_id=2